

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company-CARL BOXBERGER, ED FATZER, et al
 Farm-Weikert No. 1

SEC. 36 T. 18 R.12W
 SE SE SE

Total Depth. 3452

Comm. 5-13-53

Comp. 5-28-53


Shot or Treated.

Contractor. Virginia Drilling Co., Inc.

Issued. 8-1-53

County Barton

KANSAS



CASING:

8 5/8 set at 187'

5 1/2 set at 3452'

Elevation. 1840 KB

Production. Pot. 266 BOPD

Figures Indicate Bottom of Formations.

sand & shale	130
shale & shells	187
shale	370
red bed	530
red bed & shale	674
anhydrite	696
shale & shells	1140
salt & shale	1230
shale & shells	1420
lime & shale	1845
broken lime	1955
lime & shale	2010
lime	2070
shale	2150
shale & lime	2335
lime, shale & shells	2605
lime & shale	2668
lime	3012
lime & shale	3095
lime	3425
conglomerate	3452
Total, Depth	RTD

TOPS:

Heebner	3013
Brown lime	3131
Lansing KC	3148
Base KC	3388
Cherty conglomerate	3410

Perf. 3176½-3168½, Acid 1500 gal.

Electric log run