

503 East Murdoch,

Wichita, Kansas

Company- WELCH & OLSSON DRILLING CO.
 Farm- Eveleigh "B" No. 1

SEC. 5 T. 18 R. 12W
 NW NE NE

Total Depth. 3392'

Comm. 2-21-56


Comp. 2-28-56

Shot or Treated.

Contractor. Welch & Olsson Drllg.

Issued. 4-7-56

County Barton
 KANSAS



CASING:

8 5/8" 238' cem w/175 sx

Elevation. 1812' RB

Production. Dry

Figures indicate Bottom of Formations.

surface clay	60
red bed & sand	150
shale	350
red bed	715
anhydrite	740
shale & shells	1275
salt	1400
shale & shells with	
lime strks	1610
shale & lime	1995
lime & shale	2160
shale w/lime strks	2550
shale & shells	2675
shale & lime	2760
lime	3003
lime & shale	3107
lime	3365
lime & shale	3392
Total Depth	

Tops:

Anhydrite	715
Heebner	2996
Toronto	3014
Brown Lime	3093
Lansing	3107
Base Kansas City	3301
Chert Conglomerate	3373
Arbuckle	3377