

FEB 14 1970

2-18-12W
2-18-12W
NESWSE

W E L L L O G

DATE COMMENCED: October 22, 1969
DATE COMPLETED: October 30, 1969

Pyramid Corporation Inc.
KINZEL #2
NE/4 SW/4 SE/4
Sec. 2-T18S-R12W
Barton County, Kansas

0	-	40'	Post Rock
40	-	98'	Clay & Sand
98	-	718'	Red Bed
718	-	740'	Anhydrite
740	-	1575'	Shale & Shells
1575	-	2030'	Lime & Shale
2030	-	2585'	Shale & Lime
2585	-	2809'	Lime & Shale
2809	-	2991'	Lime
2991	-	2994'	Shale
2994	-	3010'	Lime & Shale
3010	-	3020'	Lime
3020	-	3095'	Shale
3095	-	3109'	Lime & Shale
3109	-	3336'	Lime
3336	-	3365'	Shale & Lime
3365	-	3367'	Conglomerate
3367	-	3385'	Dolomite
3385	-		RTD

ELEVATION: 1846 K.B.
oil

FORMATION TOPS	
ANHYDRITE	717
HEEBNER	2991
TORONTO	3010
DOUGLAS	3020
BROWN LIME	3095
KANSAS CITY	3109
BASE KANSAS C.	3336
CONGLOMERATE	3365
ARBUCKLE	3367
RTD	3385

SURFACE PIPE: Set 8-5/8"
good used, at 234' with
170 sacks cement.

PRODUCTION STRING: Set
good used 5 1/2" at 3375'
with 150 sacks salt saturated
pozmix.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts
and statements herein contained are true and correct to the best of his
knowledge.

Larry Curtis

Subscribed and sworn to before me this 31 day of October, 1969.

My Comm. Expires:
April 11, 1970

Robert M. Hague
Notary Public