

CASING RECORD

LOCATION Cen SW SW.

SEC 6 T 18R 12 W.

JAN 3 1928

20" 10"
 15 1-2 8 1-4
 12 1-2 6 5-8
 12 1-2 5 3-16
 TOTAL DEPTH 4390'.


FARM Eveliegh
 COMPANY Crane & Hoffine.
 CONTRACTOR S. S. Co.
 COMMENCED June 27, 1927

NO. 1 COUNTY Barton.

COMPLETED Nov. 28, 1927.

SHOT

QUARTS BETWEEN



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

ELEVATION

INITIAL PRODUCTION Dry. 1805

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 12/31/27.

Formation	Depth	Formation	Depth	Formation	Depth
soil	8	lime	1840	shale blue	3088
sand HFW 20-30	80	sand	1850	lime grey	3091
sand red HFW 90'	94	sandy lime	1870	slate blue	3099
red rock Set 20"	100	lime	1930	lime grey	3176
sandy red rock	108	shale blue	1980	lime slate brkn	3200
gympo	123	shale brown	1995	Smell of oil from	
sandy shale	135	lime	2000	3193-3200' 1 BW	3175'
slate blue	155	slate	2015	lime	3250
slate blue sandy	180	lime shells & slate	2035	slate	3255
HFW 180'		red rock	2045	lime	3293
sand grey	250	3 BW PH		shale	3300
shale sandy blue	285	lime sandy	2070	lime	3334
slate blue	338	lime broken	2085	red rock	3338
sand grey	348	shale	2104	lime	3342
red rock	371	Set 10" at 2082'		red rock	3350
Set 15 1/2" csg.		lime	2086	conglomerate	3360
red rock	695	SLM corrected from		lime	3386
8 BW 375'		2104 to 2082'		HFW 3386'	
HFW 505'		red rock	2115	6 5/8" csg. at 3389'	
Artesian water well	545'	lime	2128	lime white	3405
chalk	698	red rock	2135	water sand	3445
lime	720	Fighting cave.		lime	3460
slate green	728	lime	2145	lime dark	3480
red rock	750	shale	2150	lime hrd	3495
red rock	774	lime	2180	SLM	3521
slate blue	777	Wet hole bailing water		UR 6 5/8" csg.	
red rock	784	sandy lime	2200	lime	3535
lime	785	slate black	2210	sand water	3622
red rock	810	HFW 2180 to 2190'		HFW 3535'	
Set 12 1/2" csg. at 795'		UR 10" & cleaning out.		sand	3828
slate blue	820	lime	2253	red shale	3865
red rock	965	slate blue	2275	sandy red shale	3929
shale grey	975	shale	2365	Hole caving	
slate blue	1023	Fighting cave in shale		red shale	3960
red rock	1032	red rock	2375	shale blue	3977
slate blue	1036	slate	2380	Caving from 3929'	
red rock	1050	slate blue	2460	shale pink	3990
shale blue	1055	lime	2480	shale green	4015
shale grey	1072	slate blue	2525	Hole caving	
red rock	1082	lime	2550	shale blue	4056
shale grey	1150	shale sft	2570	Set 5 3/16" csg. at 4056'	
salt	1465	lime	2580	Caving from 4015'	
1 BW PH at 1150'		shale brown	2610	lime black	4057
lime grey	1469	lime shells & slate	2698	shale blue	4100
slate blue	1473	lime	2715	lime black	4109
lime grey	1490	shale	2745	Swabbing water	
slate grey	1510	lime	2840	shale green	4111
lime shells &		slate	2850	lime black	4115
blue slate	1615	lime	2860	shale green	4141
shale brown	1635	slate	2870	lime black	4148
slate blue	1645	lime	2880	shale	4152
sandy lime	1658	slate	2885	lime black	4178
slate blue	1670	lime	2900	shale	4187
lime	1676	Caving sine 2365'		shale gritty	4210
slate blue	1685	lime	2965	lime black	4245
lime	1718	lime sandy	2990	iron pyrites	4390
slate blue	1722	4 BW 2970'		1 BW PH 4254'	
red rock	1745	lime	3005	Total Depth	4390'.
lime	1775	8 1/4" csg. set at 2994'			
slate blue	1778	slate & lime shells	3030		
lime grey	1810	shale	3050		