


SAS
 JUL 8 0 REED
 Geological Survey
 WICHITA BRANCH

S. 12 T. 18 R. 12 E
 W

Loc. SW SW NE

County Barton

640 Acres
 N



Locate well correctly

Elev.: Gr. 1842'

DF 1844' KB 1847'

API No. 15 — 009 — 21,916
 County Number

Operator
 Brougher Oil, Inc.

Address
 P. O. Drawer 1367 Great Bend, Kansas

Well No. #2 Lease Name Tritsch

Footage Location
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Woodman & Iannitti Drlg. Geologist James C. Musgrove

Spud Date 4-27-80 Date Completed 5-6-80 Total Depth 3598' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser Salt Water Disposal

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	13-1/2"	10-3/4"	32.75	291'	Common	175	Gel 2% C.C. 3%
S.W.D.	7-7/8"	4-1/2"	10.5	3452	Common	250	Gel 2% Salt Saturated

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/1500 Gal. 15% HCL	

INITIAL PRODUCTION

Date of first production S.W.D.	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

PI

12-185-12W

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

State Geological Survey
WICHITA BRANCH
JUL 8 0 1980

May 8, 1980

Company;	Brougner Oil, Inc.
Farm;	#2 Tritsch
Location;	SW SW NE
Section;	<u>12-18-12W</u>
County;	Barton
Comm;	April 27, 1980
Compl;	May 6, 1980
Contractor;	Woodman & Iannitti Drilling Co.
Total Depth	3598'
Casing;	8 5/8 @ 291 w/175 sx. 4 1/2 @ 3452 w/250 sx.

Figures Indicate Bottom Of Formations;

225	Surface soil
291	Hard sand
349	Shale
684	Redbed
719	Anhy
1065	Redbed
1580	Shale & lime
2240	Lime & shale
2856	Lime & shale
3176	Lime & shale
3196	Lime
3274	Lime & shale
3300	Lime & shale
3330	Lime
3375	Lime & shale
3419	Lime
3428	Lime & arbuckle
3449	Lime & shale
3598	Arbuckle

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman