

15-009-21569

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.

State Geological Survey
 WICHITA BRANCH
KANSAS DRILLERS LOG

S. 2 T. 18 R. 11 ¹³ _W
 Loc. SE SE NW
 County Barton

API No. 15 — 009 — 21,569
 County Number

Operator
Icer Addis

Address
P. O. Box 8038 Wichita, Kansas 67208


Well No. #3 Lease Name Tindall

Footage Location
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Duke Drilling Co., Inc. Geologist Richard M. Foley

Spud Date February 16, 1979 Total Depth 3,334' P.B.T.D.

Date Completed February 21, 1979 Oil Purchaser Dry Hole



Elev.: Gr. _____
 DF _____ KB 1,805

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	28#	443'	50-50 Pozmix	265	2% Gel, 3% CaCh

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Dry Hole Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ICER ADDIS DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. #3 Lease Name TINDALL DRY HOLE

S 2 T 18 R 13 W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	690			
Topeka	2,688			
Heebner	2,976			
Toronto	2,994			
Douglas	3,004			
Brown Lime	3,069			
Lansing	3,080			
Base Kansas City	3,316			
Arbuckle	3,323			
Rotary Total Depth	3,334			
DST #1: Open 45" (30-30-15-30) Weak blow 6"; recovered 2' very slight oil specked mud. ISIP 30#, FSIP 62#, IFP 21#, FFP 21#	3,311	3,325		
DST #2: Open 60" (30-30-30-30) Recovered 320' muddy water; ISIP 915#, FSIP 863 #, IFP 52-104#, FFP 135-177#	3,311	3,334		
Low structural position and lack of shows. Plugged and Abandoned at RTD	3,334			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Icer Addis
 Icer Addis Signature
 Owner-Operator
 Title
 March 2, 1979
 Date

847-01