

CONTINENTAL Oil Co.  
E.J. Eveleigh No. 1.

SEC. 11 T. 18 R. 13 W.  
SEc NW  
330' N & 330' W of Center

Total Depth. 3374 G.Level.  
Comm. 11-3-41 Comp. 11-19-41  
Shot or Treated.  
Contractor.  
Issued. 1-10-42

County Barton.



CASING.

103/4" 489

Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

surface clay	30
clay yellow	200
clay blue	380
sand	390
red bed and shells	496
red bed	680
white water sand	720
red bed	970
shale	1220
shale and salt	1507
shale and lime shells	1558
shale	1568
lime	1707
lime and shale	1810
lime	1985
broken lime	2085
lime	2110
broken lime	2510
shale	2584
shale and lime	2760
shale	2830
lime	2915
lime soft	2921
lime	3012
broken lime	3075
lime	3138
lime and shale	3146
lime soft	3152
lime	3163
lime soft	3176
lime	3193
lime hard	3231
lime	3303
lime soft	3355
lime rough	
lime soft	3360
Total Depth from ground level	3374

Top of Kansas City lime 3064

Cored from 3356 to 3374 Recovering 10' of Arbuckle lime with no  
show of oil but with odor of sulphur.

plugged and abd. Nov. 20, 1941

Note - All of the above footages are calculated from the ground level