


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TOKLAN PRODUCTION CO.
Farm- Traylor No. 1

SEC. 34 T. 18 R. 13W
SE SW SW

Total Depth. 3432
Comm. 5-18-53 Comp. 5-29-53
Shot or Treated.
Contractor. K & E Drilling Co.
Issued. 9-5-53

County Barton
KANSAS



CASING:
8 5/8 @ 233' w/ 150 sx cem.
5 1/2 @ 3441.3' w/ 75 sx cem.

Elevation. 1897 DF

Production. Pump 58 BOPD

Figures indicate Bottom of Formations.

surface soil & lime rock	100
lime rock & shale	233
shale & shells	496
red bed & shale	790
anhydrite	820
red bed & shale	1075
shale & shells	1520
lime & shale	1640
shale & shells	1820
lime & shale	3220
lime	3240
lime & shale	3405
lime, chert & shale	3432
Total Depth	

TOPS:

Anhydrite	790
Heebner	3065
Toronto	3075
Douglas shale	3090
Brown lime	3153
Lansing	3167
Conglomerate	3401
Ambuckle	3422

DST #1: 3171-3240, open 1 hr. wk blo
9 min. rec. 15' mud w/ few oil specks
BHP 0#

DST #2: 3291-3338, open 1 hr. fr to
wk blo thruout, rec 230# HO&GCM
BHP 400#

DST #3: 3370-3426, open 1 hr. wk blo
10 min. rec. 33' OCM, BHP 230# rising

Acidized:
3123-27 1350 gals 15%
3314-20 600 gals 15%
3172-76 750 gals 15%

Perf:
3314-20 w/ 24
3326-40 w/ 56
3172-76 w/ 17
3216-22 w/ 22
3226-30 w/ 17

Driller's measurements from Rotary Bushings
above 8-5/8" Bradenhead 6.4'