


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. MURFIN & SMALL
Farm-Curry No. 2

SEC. 33 T. 18 R.13W
NW SE SE

Total Depth. 3475
Comm. 10-18-53 Comp. 10-29-53
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 12-26-53

County Barton
KANSAS



CASING:
8 5/8 209'

Elevation. 1877 KB

Production. Dry

Figures Indicate Bottom of Formations.

shale, sand & shells	485
shale & shells	500
red bed	778
anhydrite	797
red rock & shale	1115
salt & shells	1500
shale & shells	1600
lime & shale	2910
lime	3475
Total Depth	

TOPS:	
Heebner	3047
Toronto	3060
Douglas	3081
Brown lime	3136
Lansing	3149
Conglomerate	3384
Arbuckle	3475

DST #1: 3152-80, open 10 min. rec.
7 1/2' mud, BHP 0#

DST #2: 3269-3320, open 50 min. weak
blow 26 min. rec. 32' mud w/ rainbow,
BHP 840#, IFP 80#, FFP 100#

DST #3: 3370-3403, weak blow 6 min.
rec. 10' mud w/ rainbow, BHP 160#

DST #4: 3403-07, failed to get to
bottom.

DST #5: 3401-07, weak blow 11 min.
rec 15', BHP 610#

DST #6: 3404-3427, weak blow 2 min.
rec 12' mud, BHP 660#