

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- WESTERN PETROLEUM CO.
Farm- Doonan No. 1

SEC. 21 T. 18 R. 13W
NE NW SW

Total Depth. 3354'
Comm. 7-2-61 Comp. 7-9-61
Shot or Treated.
Contractor. Western Pet.
Issued. 9-16-61

County Barton

KANSAS



Elevation. 1826' DF

Production. Dry

CASING:
8 5/8" 754'

Figures Indicate Bottom of Formations.

anhydrite	782
shale & shells	1570
shale & lime	1808
lime w/shale streaks	1990
lime & shale	2175
shale & lime	2670
lime w/shale strks	2740
lime	2993
Heebner shale	2997
lime	3017
Douglas shale & sand	3055
lime	3321
lime & shale	3354 RTD
Total Depth	

TOPS:	
Anhydrite	744
Heebner	2994
Toronto	3004
Douglas	3019
Iatan	3081
Lansing	3099
Conglomerate	3319
Arbuckle	3340

DST #1 3126-67', op 1½ hrs, fair blow,
rec. 360' formation water, NS IBHP
1005#/30 min, FBHP 645#/30 min, IFP 0#,
FFP 140#, HH 1710#.

DST #2 3339-44', op 35 min, weak blow
for 5 min. Rec. 6' rotary mud. NS All
pressures 0#/30 min, HH 1825#.

DST #3 3344-54', op 1½ hr, good blow,
Rec. 1080' formation water w/sulphur
odor. IBHP 1005#/30 min, FBHP 960#/30 min,
IFP 0#, FFP 415#/ HH 1830#.