

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY
Farm - L. Trester No. 1

SEC. 21 T. 18S R1W
SW SW SW

Total Depth. 3389'
Comm. 6/6/48 Comp. 7/16/48
Shot or Treated.
Contractor. Brunson & Powell
Issued. 9/4/48

County. Barton
KANSAS



CASING: 10 3/4" @ 797'; cem. w/550 sax
7" @ 3372'; cem. w/75 sax

Elevation. 1870 Ind.

Production. Pmp 28 BO, 3 BW

Figures Indicate Bottom of Formations.

clay, shale & iron	225
shale, shells & iron	350
shale	450
red bed	790
anhydrite	830
shale & shells	1180
shale	1410
salt	1510
shale & lime	1660
broken lime	1715
shale & lime	1775
lime	1935
shale & broken lime	2010
shale & shells	2250
shale	2340
broken lime	2505
shale & lime	2826
broken lime	2855
lime	2915
shale	2950
lime	3025
shale & lime	3060
lime	3375
arbuckle lime	3389
Total Depth	

7/16/48 hours.
Completed. Pumped 28 BO,
3 BW in 24 hours.

Tops:	
Ft. Riley	1775
Topeka	2790
Heebner	3036
Lansing	3135
Arbuckle	3369
Conglomerate	3364

6/29/48 Dumped 1 Bbl acid loaded
with 400' water. Swabbed
out, no results. Perf.
with Lane Wells from 3371
to 3375. 48 holes. No
result.

6/30/48 Acidized w/500 gals with
135 BW load. Treated at
1450# pressure. Swabbed
and bailed dry, tested for
30 minutes, 20 gal. oil
and small amount of water.

7/1/48 Acidized w/1000 gal. did
not break pressure down
(1450'), swabbed and bailed
down, no increase in oil.

7/3/48 At 3389', swabbed and
tested 3 BOPH. 1000' fill-
up in one hour.

7/4/48 Acidized w/500 gal., max.
pressure 850#, dropped to
0 after treatment, swabbed
and bailed down, tested 3 1/2
BOPH, no water.

7/13/48 Pumped 74 BO, 10 BW in 17