

State Kansas County Rice

Company Messman-Rinehart Oil Co. Well No. 1

Farm Cramm


Survey

Block No. Sec. 13 Twp. 18 S Range 9 W

Co-Ord. Elev. 1741' K/B

SW SW NW

M-R Rig



50% - A. A. Seeligson, Jr.
25% - Chicago Group
25% - Messman-Rinehart Oil Co.

3400' Arbuckle test to be comm. by 11/10/60

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 330 Ft. from S. Line

330 Ft. from W. Line Ft. from E. Line

Date	Depth	
10/21/60		M.I.R.T.
10/22		Spud - 8-5/8" @ 206' w/100 sx
		cem., 2 gel., 2 c.c.,
		P.D. @ 3:00 p.m. 10/22/60
10/24	1380	Drlg. (#2 @ 1315)
		(Sho gas @ 1290)
10/25	1830	Drlg. (#3 @ 1685)
10/26	2400	Drlg. (#4 @ 2385)
10/27	2685	Drlg. (#5 @ 2660) mudding up

Date	Depth	
		DL10' (12 G) 692599
10/28	2980	Drlg. (#6 @ 2936)
	2743	Heebner (-1002)
	2775	Douglas (-1034)
	2868	Br. Lm. (-1127)
	2891	Lansing (-1150)
	3020	Drlg.
10/29	3160	Drlg. (#7 @ 3144)
	3262	Congl. (Sp.) (-1521)
	3280	Simpson (-1539)
	3325	Arbuckle (-1584)
10/30	3350	Drlg.
	3365	R.T.D. (Ran Log)

D.S.T. #1 (Ft. Riley) Op 1 hr., wk bl.

Rec. 15' mud, ISIP 410#,

FSIP 75#, FP 25-25#,

Log Calculations: Simpson - 60% wtr.

Zone @ 2200' (Tarkio) too thin

D & A 11/1/60

Log Tops:

2742	Heebner (-1001)
2774	Douglas (-1033)
2868	Brown Lime (-1127)
2892	Lansing (-1151)
3261	Cherty Cong. (-1520)
3280	Sp. Sd. (-1539)
3324	Arbuckle (-1583)