

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - CITIES SERVICE OIL COMPANY
Farm - Miller "G" No. 4

SEC. 11 T. 18 R. 14W
NE SW NE
990' North 990' East
of center

Total Depth. 3379'
Comm. 11-21-48 Comp. 12-11-48
Shot or Treated.
Contractor. Corbett & Barbour Drilling
Issued. 2-12-49

County. Barton

KANSAS



Elevation. 1892 feet

Production. Phys. Pot. 192 oil
no wtr, 24 hr

CASING:

8 5/8" 843' w/400 sx cement
5 1/2" 3372' w/125 sx cement

Figures Indicate Bottom of Formations.

clay, sand	40
sand, clay, anhydrite	325
shale, shells	383
sand, shells	440
shale, shells	490
red bed	620
pyrite	645
shale, shells	690
red bed	835
anhydrite	843
anhydrite, shale	945
shale, shells	1225
salt	1510
shale, shells	1575
lime, shale	2035
lime	2355
shale	2520
shale, lime strks	2660
shale, lime	2770
lime	3377
3377 Rotary T.D. = 3372 SLM	
lime	3379
Total depth	

Tops: corr.

Lansing	3136
Cherty Conglomerate	3338
Erosional Arbuckle	3369
Arbuckle	3370
Penetration	3379
Fillup	
125' oil in 2 hr	
160' oil in 4 hr	
300' oil in 10 hr	