

Bruce Benson

PROSPECT	Yukon	YEAR	1976	COUNTY	Barton	STATE
LEASE	Indian	WELL NO.	1	WELL LOCATION	SW SW SW	
SITE LEASE DESCRIPTION		SW/4	Sec. 36-18-15	CODE		
OPERATOR	Beren Corporation		ELEVATION:	GR	1943	
CONTRACTOR	Company Tools			DF		
GEOLOGIST				KB	1948	
DEVELOPMENT WELL	PROSPECT TEST WELL X		NOTIFY	Bruce Benson - BMG, Inc.		
OWNERSHIP	1976 Program			1400 Metробанк Bldg.		
IDENTIFICATION	Test well - washdown			475 17th St.		
				Denver, Colorado 80202		
			PHONE:	(303) 893-0883		

11/15/76      Tubing at 1791'. Treated with 1000 gallons, 550#, 2½ bbls./min.

11/18/76      Casing 90#.

11/19/76      Casing 108#. Blow down ½ minute.

11/20/76      Casing 240#. 2:00 p.m. 270# casing.

11/22/76      Casing 245#

12/29/76      Fraced. Maximum pressure 1900#, minimum pressure 1250#, Average rate BPM 21.8, ISIP 500#. In 10 minutes 500#. Frac down casing w/10,000 gal 3% acid and 10,000# 20/40 sand & 16 ball sealers. Treated @ 21 BPM 1200#. When balls hit, pressure increased to 1900# and broke back to 1600#. ISIP 500#, 20 min. 250#. S.I.

1/30/76      Ran 2" tubing. Ran GR-CC1 and tagged bottom @ 1837' bottom perf in 1836. Gamma log indicates sand went into perfs. Ran swab 700 feet to fluid. Swabbed till 5 PM. CP 50#.

12/31/76      This AM had 100# CP & 40# TP.

1/ 3/77      420# tubing, 360# casing. Blew down. 9:30 started kicking off.

1/ 4/77      CP & TP both 400#. Opened up @ 9:00 AM, kicked off and flowed. 10:30 CP was 120# flowing a lot of water. 12:00 swabbing and have 300' of fluid in the hole.

1/ 5/77      CP & TP both 440#. Blew down in 5 min. to 60#. Light flow of gas. Then started building up some pressure.

1/ 6/77      Tore down and moved off.

PROSPECT Kuhlman YEAR 1976  
 LEASE Kuhlman WELL NO. 1 WELL LOCATION SW SW SW COUNTY Barton STATE Ks  
 & SITE LEASE DESCRIPTION SW/4 Sec. 36-18-15 CODE

OPERATOR Beren Corporation

ELEVATION: GR 1943

CONTRACTOR Company Tools

DF

GEOLOGIST

KB 1948

DEVELOPMENT WELL PROSPECT TEST WELL X

NOTIFY Bruce Benson - BMG. Inc.

OWNERSHIP 1976 Program

1400 Metrobank Bldg.

IDENTIFICATION Test well - washdown

475 17th St.

TOPS:

LOG TOPS

Herrington 1814 (+134)  
 Winfield 1864 (+ 84)

MOVING IN & RIGGING UP October 18, 1976 SPUD

SET 8-5/8 @ 933' w/

DATE DEPTH DST

10/20/76 Set 4" @ 1913' with 100 sx.

10/25/76 Logged