


Pl.
granite 3308
gas sd 3473

INTERSTATE PRODUCTION
Schmidt No. 1.

SEC. 9 T. 18 R. 16W
C SE $\frac{1}{4}$

Total Depth. 3559'
Conn. 5-15-36 Comp. 7-3-36
Shot or Treated.
Contractor, Haskin Brothers.
Issued. 7-25-36

County. Rush



CASING:
20 " 94'
15 $\frac{1}{2}$ " 405'
12 $\frac{1}{2}$ " 1007'
10 " 2357'
6 " 3235'
7 " 3473'

Elevation. 1943

Production. 5,600,000 Gas.

Figures Indicate Bottom of Formations.

collar	11	line	2425	quartzite rose colored
soil	18	line & shale breaks	2440	quartz & black & white
sand	50	line $\frac{1}{4}$ BW	2480	Mica 3545
shale	85	shale blue & shells	2500	quartzite rose colored
shale blue	100	line & blue shale		quartz & black & white
water sand HFV	130	breaks	2570	Mica 3559
shale brown	140	line & shale breaks	2635	Total Depth
shale blue	145	shale blue	2660	
shale red	205	lime	2675	
shale blue	220	shale blue	2695	
shale red	230	line & shale	2810	
shale blue	325	shale brown	2815	
lime	330	shale blue & shells	2870	
shale blue	410	line	2885	
sand wtr flowing	525	shale blue & shells	2905	
red rock	535	line	2935	
shale red	560	shale light	2945	
sand more water	625	line & shale blue	2995	
shale red	995	sand line 1 BW	3010	
lime	1035	line & shale	3075	
shale red	1230	line & shale breaks	3100	
shale blue & shells	1275	shale light	3105	
shale brown	1330	sandy line 3 BW	3160	
shale blue	1380	line & shale breaks	3225	
lime	1400	shale brown	3235	
shale blue	1425	shale blue	3250	
shale brown	1445	line	3255	
salt blue	1500	line & shale blue		
salt	1705	breaks	3260	
line & shale dark	1770	white sdy line	3275	
lime	1800	line & shale	3290	
shale red	1805	shale brown	3295	
line & shale breaks	1855	lime dark	3345	
red rock	1860	1 BW 3350-60		
lime	1895	sdv line	3400	
show gas 1870-75		line	3455	
shale light 3 BW	1900	shale red	3460	
lime	1965	line	3465	
red rock	1985	shale blue & shells	3475	
lime	2120	gas sand	3474	
shale red	2125	sdv lime	3483	
lime	2135	line & blue shale		
shale blue	2140	breaks	3486	
lime	2170	shale brown	3488	
shale blue	2185	shale blue	3490	
lime	2190	gas sand	3498	
shale brown	2195	lime hard	3506	
lime	2240	lime brown Mica	3506	
shale brown	2250	quartzite Mica	3511	
lime	2260	quartzite black &		
line & shale	2315	white Mica & rose		
red rock	2325	colored quartz	3520	
lime	2330	quartzite black &		
red rock	2335	white Mica & more		
lime	2410	rose colored quartz	3524	
red rock & shale		quartzite Mica &		
blue	2420	quartz	3534	

3473
1943
1530

3490