


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

MORGAN & FLYNN OIL CO.  
Koriel No. 3-B.

SEC. 23 T. 18 R. 16W.  
Cen N/2 SW

Total Depth, 3550  
Comm. 4-1-37 Comp. 4-29-37  
Shot or Treated.  
Contractor, Herndon Drlg. Co.  
Issued, 7-3-37

County Rush.



CASING.

7" 3496'

Elevation.

Production, Pot. 517 B.  
45,000,000 gas.

Figures Indicate Bottom of Formations.

soil and sand	90
shale	211
shale and shells	412
sand	505
red rock and shale	550
sand	590
shale and red rock	665
shale and shells	820
red rock and shale	975
anhydrite	1020
shale and shells	1035
shale and salt	1310
shale shells and salt	1535
shale and shells	1685
broken lime	1760
lime	1870
broken lime	1900
lime	1935
broken lime	2035
lime	2310
broken lime	2690
lime	2815
broken lime	2865
lime	3105
broken lime	3225
lime	3490
shale red	3493
sand showing oil	3508
Standardized	
sand gas	3509
sand Oil Pay 3534-50	3550
Total Depth,	

Good oil pay 3534-36  
3548-50

Well made 517 bbls of oil  
45 Million cu ft gas. (later Increased to 60 Million.  
( didnt take rock pressure.)

oil shows in core at 3496-3508