


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

OLNEY F. FLYNN  
Crowell No. 3

SEC. 23 T. 18 R. 16W  
SE SW NE  
990' f WL 330' f SL NE $\frac{1}{4}$

Total Depth. 3553  
Comm. 8-3-41 Comp. 9-3-41  
Shot or Treated.  
Contractor. J.A. Aylward  
Issued. 11-1-41

County Rush.



CASING.

10" 979' cemented.  
7" 3545 cemented.

Elevation.

Production. Pot. 1272 B.

Figuros Indicate Bottom of Formations

surface clay	25
sand	75
sand gravel	115
red bed shale	340
shale and limo	383
shale	395
sand	570
sand and shale	610
rod bed and shale	635
rod rock & sdy shale	945
rod rock	972
anhydrito	1005
shale	1010
rod rock and shale	1240
shale and shells	1315
shale	1430
salt and shale	1700
broken lime	1835
sdv lime	1860
lime and shale	2025
broken lime	2050
lime	2070
shale	2100
limo	2166
shale and lime	2235
shale and shells	2330
shale limo and shells	2425
broken lime	2510
shale and shells	2595
shale and limo shells	2720
lime and shale	2870
limo	3340
cherty lime	3370
limo	3455
limo rod rock & shale	3468
lime and shale	3504
hard sand	3505
sand and lime	3513
conglomerate	3520
limo	3549
sand	3553

Total Depth.

Hole filled up from 1200 to 2000 when drilled to 3549  
Lane Wells gun perforated with 47 shots 3524 $\frac{1}{2}$ -3535.  
12 shots 3534 $\frac{1}{2}$ -3538