


THE CARTER OIL CO.
Wm. Rubart No. 1.

SEC. 24 T. 18 R. 16W
SEc SE
330' fr S & E Lines

Total Depth. 3543'
Comm. 3-4-37 Comp. 4-10-37
Shot or Treated. 50 Qts. 3527-38
Contractor. Parker Drlg.Co.
Issued. 5-15-37

County. Rush



Elevation. 1920 ✓

ROTARY
CASING:
15 1/2" 226'
10 " 927'
7 " 3533'

Production. Pot. 40 Bbls.

Figures Indicate Bottom of Formations. 40 BW., 6,000,000 Gas.

surface	12
sdv shale	97
sand, clay	241
shale, sholls	350
wtr sand	356
shale, wtr sand	590
shale, shells	706
shale	788
shale, shells	920
anhydrite	950
red bed	975
shale, shells	1300
brkn lime, shale	1380
shale, lime shells	1455
brkn lime	1485
shale, lime	1505
shale, salt	1600
brkn lime	1815
lime	1847
sdv lime	1930
brkn lime	2042
lime hrd	2080
lime, shale	2125
lime	2248
shale, lime, red rock	2332
brkn lime, shale	2542
brkn lime, shale, red rock	2637
brkn lime, shale	2860
brkn lime	2900
lime	2930
brkn lime	3008
lime, shale	3060
lime	3080
red rock	3090
lime	3170
brkn lime, shale	3250
lime hrd	3293
lime	3302
shale, lime	3310
lime	3465
shale	3482
sand	3490
cored sand	3496
cored sand	3541
cored granite	3543
Total Depth.	

3482
1920
1562

Reagan(gas) 3482-3519
Reagan(oil) 3519-3538

30 shots 3533-38
50 Qts. 3527-38