


SCHERMERHORN-WINTON-SHELL (O.R.)
C. Moore No. 1.

SEC. 25 T. 18 R. 16W
NWc NW
330' fr NL 440' fr WL NW $\frac{1}{4}$

Total Depth. 3558' P.B. 3556'
Comm. 11-7-36 Comp. 2-11-37
Shot or Treated.
Contractor. Haskins Bros.
Issued. 2-27-37

County. Rush.

CASING:
20" 78'
16" 365'
13 3/8" 965'
10 5/4" 2375' UR 2384'
8 5/8" 3300'
7" 3530'



El. 1931

Production. Pot. 108 B.

Figures Indicate Bottom of Formations. No water.

cellar	10	lime	2135	shale	3450
shale	36	shale	2140	lime	3464
sand	75	lime	2150	shale	3469
shale red	95	shale	2160	shale & lime shells	3483
sand	100	lime	2175	lime	3494
shale	115	shale	2180	V.C. shale & lime	
red rock	135	lime & shale	2190	shells	3500
shale	160	lime	2285	shale & shells	3506
shale red	200	shale	2305	lime	3511
shale	220	lime	2350	shale	3515
sand	235	shale	2355	lime	3530
HFW 220-30		lime	2360	sand	3539
shale	305	shale & shells	2365	sdv lime	3551
sand	330	shale	2385	sand (3553-3535SLC)	3553
sdv lime	335	lime	2410	Gas 3533-34 Est. $\frac{1}{2}$ MCF (Corr)	
shale	380	700' water in hole		Oil 3534-35 Corr.	
sand	480	shale	2420	sand	3535-3539
shale red	495	lime	2450	conglomerate?	3546
red rock	525	shale & shells	2535	600' oil @ 3546	
sand	555	lime	2545	sand	3558
red rock	575	shale	2570	1200' oil 3551	
red shale & sand	615	shale & shells	2590	2000' oil 3556-12 hrs.	
shale red	635	shale	2640	Swab 35 oil No wtr 7 hrs.	
red rock	680	lime	2660	Total Depth.	
shale red	912	shale	2695	Plugged Back 3556'	
shale	915	lime	2710		
shale red	940	shale	2715		
anhydrite	965	lime	2760		
anhydrite & lime	980	shale	2770	Shot 20 Qts. 3548-53	
lime	995	lime	2785	Shot 7 Qts. 3512-25	
shale	1240	shale	2800	Pump & Flow 108 Oil & O	
sdv lime	1275	lime	2810	Water-24 hour potential	
shale	1385	shale	2830	Small amount of gas,	
salt	1660	lime	2890		
shale	1670	shale	2905		
lime	1685	lime	3035		
shale	1690	sdv lime	3045		
lime	1705	1 BWPB 3035-45			
lime & shale	1720	lime	3120		
missing	1725	sdv lime	3145		
shale	1735	2 BWPB 3120-30			
lime	1775	lime	3190		
shale	1780	shale	3195		
lime	1790	lime	3215		
shale & shells	1800	shale	3220		
shale	1805	lime	3223		
lime	1855	shale	3245		
Show gas 1840-45		lime	3273		
shale	1870	sdv lime	3285		
lime	1880	1 BWPB 3273-85			
sdv lime	1900	lime	3340		
2 BWPB 1880-90		sdv lime	3345		
shale	1915	4 BWPB 3340-45			
shale red	1940	lime	3370		
lime	1960	HFW 3345-52			
1 BWPB 1960-70		sdv lime	3375		
sdv lime	2025	lime	3398		
lime	2110	lime & shale	3405		
shale	2115	lime	3447		

3535
1931
1604