


SCHERMERHORN OIL CORP.
Schroeder No. 2.

SEC. 36 T.18 R.16W
Con NE $\frac{1}{4}$

Total Depth. 3657' P.B. 3653'
Comm. 12-22-36 Comp. 3-7-37
Shot or Treated.
Contractor. Corbett-Barbour Drlg.Co.
Issued. 3-27-37

County. Rush



El. 2013

CASING:

20 " 1 Joint Pulled
15 $\frac{1}{2}$ " 462' Cemented
12 $\frac{1}{2}$ " 1024' Left in
10 " 2458' Pulled
8 $\frac{1}{4}$ " 3389' Pulled
7 " 3624' Cemented

Production. Pot. 356 B.
24 hr swab test

Figures Indicate Bottom of Formations,

cellar	10	lime	2240	shale	3428
mud yellow	20	shale blue	2262	lime	3554
shale blue	95	shale red	2275	HFW 3435	
gyp shells & shale	110	lime	2320	shale blue	3558
mud white	130	shale red	2341	lime	3566
sand water	140	lime	2350	conglomerate	3631
shale blue	180	shale red	2355	Show sand 3622-25	
red rock	200	lime	2375	shell	
shale grey	230	shale red	2410	sand	3640
water sand	270	lime	2435	Show oil 3631-40	
HFW 235		broken	2440	Steel line Corr 3640-34	
red rock	280	lime	2455	sand	3645
shale blue	335	shale red	2465	sdv lime Sh oil	3651
sand	355	lime	2530	sand Oil	3654
shale blue	465	shale blue	2553	sand Water	3657
Hole making 12 B ^{PH}		lime	2560	Total Depth.	
sand	500	shale blue	2585		
Hole filling up		lime	2594		
shale red	515	shale blue	2620		
sand	535	lime	2650		
shale red	545	shale blue	2660		
sand	560	shells & shale	2680		
shale red	600	shale blue	2700		
sand	625	lime	2712		
shale red	1030	shale blue	2720		
anhydrite	1065	lime	2730		
shale blue	1070	shale blue	2740		
red rock	1125	lime	2760		
shale red	1290	shale blue	2798		
shale blue	1325	lime	2835		
shale red	1390	shale blue	2845		
shale blue	1468	lime	2850		
salt	1725	shale blue	2855		
shale blue	1740	lime	2865		
salt	1755	red rock	2870		
shale blue	1795	shale red	2877		
lime	1815	shale blue	2885		
shale blue	1820	lime	2900		
lime	1873	shale blue	2920		
shale	1890	lime	2932		
lime	1910	shale blue	2936		
shale blue	1913	lime	2942		
lime	1916	shale blue	2950		
shale red	1920	lime	2980		
lime	1965	shale blue	3000		
shale blue	1972	lime	3006		
lime	2028	shale drk	3023		
6 BW 1990-2000		lime	3270		
shale red	2045	2 $\frac{1}{2}$ BW 3205			
shale blue	2050	shale blue	3275		
lime	2067	lime	3293		
shale blue	2072	shale blue	3295		
lime	2095	lime	3300		
lime sdv	2100	shale blue	3330		
lime	2200	lime	3405		
shale blue	2206	HFW 3370-80			
lime	2210	lime brown	3410		
shale blue	2217	lime	3418		