

Computer Inventoried



J. Copeland Landes

Exploration Geologist

8-18-18W
KCC

JAN 11 1991

1115 Thomas
Denton, Texas 76201

817-383-4035

August 25, 1989

BALCRON OIL COMPANY
P. O. Box 21017
Billings, Montana 59104

15-165-21,487

Re: BALCRON OIL COMPANY
1 - 8 John K
1230' F W L 330' F S L
Section 8 - T18S - R18W
Rush County, Kansas

GEOLOGICAL REPORT

Gentlemen,

Following is the pertinent information concerning the above captioned well:

Contractor:	Duke Drilling Co. Rig 4	Pusher:	Jay Schneider
Spud:	August 11, 1989	Complete:	August 17, 1989
Surface:	1003' @ 1018'	Mud:	M S I
D S T:	None	Log:	Great Guns
Elevation:	2085' K B	Long String:	None
Geologist:	J. Copeland Landes		

BIT RECORD

# 1	7 7/8"	W/M	51Cf	1022 - 4250
-----	--------	-----	------	-------------

SEP 07 1989
KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

8-18-18W

BALCRON OIL COMPANY
1 - 8 John K
Rush County, Kansas

August 25, 1989

GEOLOGICAL TOPS

<u>Formation</u>	<u>Sample</u>	<u>Electric Log</u>
ANHYDRITE	1253 (832)	1242 (843)
TOPEKA	3119 (-1034)	3118 (-1033)
HEEBNER	3439 (-1354)	3437 (-1352)
TORONTO	3455 (-1370)	3458 (-1373)
LANSING-KANASA CITY	3493 (-1408)	3488 (-1403)
BASE KANSAS CITY	3754 (-1669)	3754 (-1669)
MARMATON	3804 (-1719)	3804 (-1719)
CONGLOMERATE	3842 (-1757)	3844 (-1759)
ARBUCKLE	3920 (-1835)	3920 (-1835)
REAGAN SAND	4180 (-2095)	4178 (-2093)
GRANITE SAND	4208 (-2123)	4208 (-2123)
R T D	4250	L T D 4249


ZONES OF INTEREST

There were no shows of oil or gas encountered in drilling this well, and therefore no zones of interest.

CONCLUSION

This well ran low structurally to the wells with shows in the area, encountered no shows, and was plugged and abandoned.

Sincerely,



J. COPELAND LANDES