

State

Kansas

County

Barton

Company

Messman-Rinehart Oil Co.

Well No.

1

Farm

Laudick "A"

Survey

Block No.

Sec.

18

Twp. 18 S

Range 13 W

Co-Ord.


Elev.

1857' K/B

1855' D/F

SE/4 NE/4 SW/4

M-R Rig



1/4 - Chicago Group (Anderson, McDermott, McNeill)

1/4 - L. J. Plym

1/4 - A. A. Seeligson, Jr.

1/4 - M-R Oil Co.

DHM (\$2,500.) Colo. O&G

25' into Arb. (or -1510)

test to be comm. by 11/10/64

NOTE: Show Sketch of Lease and Well Location in Above Space

990

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

330

Ft. from E. Line

Date

Depth

10/20/64

M.I.R.T.

10/21

Spud - 8-5/8" @ 785' w/330 sx
cement, 9 gel., 7 c.c., P.D.

@ 4:00 a.m. 10/22/64

10/23

1020

S.U.S. @ 4:00 a.m.

777

Anhydrite (+1080)

10/24

1940

Drlg. (#2 @ 1848)

10/26

2845

Drlg.

10/27

3045

Drlg.

Date	Depth	692987
	2732	Topeka (-875)
	2936	Queen Hill (-1079)
	3020	Heebner (-1163)
	3102	Brown Lime (-1245)
	3117	Lansing (-1260)
DST #1 - 3181-3220 - op 1 hr., good bl TO		
	Rec.	486' wtr., BHP 1117=983#
	FP	78-256#
10/29	3347	Drlg.
	3340	Reworked Arbuckle (-1483) SO
DST #2 - 3341-47' - Op 30", wk. bl. for 6"		
	& died, Rec. 30' mud w/few specks	
	oil, BHP 670=311#, FP 23-32#, Temp 106°	
(Attempted to DST 3347=62' - packer wouldn't hold		
DST #3 - 3350-62' - Op 30", wk. bl. for 8"		
	Rec.	10' mud, BHP 62-47#, FP23-31
	3374	Arbuckle (-1517)
	3390	R.T.D. (Ran log)
	D & A 10/31/64	