

Computer Inventoried

SCOTT CORSAIR

PETROLEUM GEOLOGIST

KANSAS LICENSE NO. 55

210 Avenue A P.O. Box 6

Bazine, Ks 67516

785-398-2270 Mobile 785-731-5060

FAX 785-398-2586

GEOLOGICAL REPORT

AMERICAN WARRIOR, INC.

YOUNG #1-12

800' FSL & 2500' FEL

Section 12-18S-21W

Ness County, Kansas

NW - SW - SE

OPERATOR: AMERICAN WARRIOR, INC.
WELL: YOUNG NO. 1-12
API NO.: 15-135-24080
LOCATION: 800' FSL & 2500' FEL, SEC. 13-18S-21W
WELLSITE: FARMGROUND
COMMENCED: AUGUST 21, 1999
COMPLETED: AUGUST 23, 1999
ELEVATIONS: 2097' GL ; 2105' KB
TOTAL DEPTH: 2284' (DRILLER); 2284 (LOGGER)
CASING: SURFACE: 8 5/8 @ 227' W/150 SKS
 PRODUCTION: 4 1/2 @ 2283' W/210 SKS
SAMPLES: NONE
LOGS: DUAL INDUCTION, DUAL COMPENSATED
 POROSITY, BY LOG-TECH
DRILLSTEM TESTS: NONE
CONTRACTOR: DISCOVERY DRILLING (RIG 2)

REMARKS: Geological supervision: 2100' - T.D.

FORMATION TOPS	ELECTRICAL LOG SUBSEA		SAMPLES SUBSEA
Anhydrite	1320	+785	
Chase	2174	- 69	

SUMMARY AND RECOMMENDATIONS

This well was drilled as a Chase gas well. No samples were examined. Log analysis and structural position indicate probable commercial gas production from the Chase. Based upon available data 4 ½" production casing was set.

Pipe was set 1 foot off bottom @ 2283'. The following zones are recommended for testing.

1. Chase 2236-2240
2. Chase 2180-2186

Measurements were taken from rotary kelly bushing (8 feet above ground level).
Logger's measurements are taken as correct.

Respectfully,



Scott Corsair
Petroleum Geologist

