

TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

American Warrior Inc
Box 399
Garden City Ks 67846
ATTN: Cecil O'Brate

Phyllis # 1-32
32-18-21-Ness-Ks
Job Ticket: 38134 **DST#: 1**
Test Start: 2010.02.22 @ 20:15:15

GENERAL INFORMATION:


Formation: **Miss**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 22:22:45
Time Test Ended: 01:56:45
Test Type: Conventional Bottom Hole
Tester: Dan Bangle
Unit No: 38
Interval: **4212.00 ft (KB) To 4222.00 ft (KB) (TVD)**
Reference Elevations: 2127.00 ft (KB)
Total Depth: 4222.00 ft (KB) (TVD) 2119.00 ft (CF)
Hole Diameter: 7.88 inches Hole Condition: Good KB to GR/CF: 8.00 ft

Serial #: 8354 **Inside**
Press@RunDepth: 128.33 psig @ 4213.00 ft (KB) Capacity: 8000.00 psig
Start Date: 2010.02.22 End Date: 2010.02.23 Last Calib.: 2010.02.23
Start Time: 20:15:16 End Time: 01:56:45 Time On Btm: 2010.02.22 @ 22:18:45
Time Off Btm: 2010.02.23 @ 00:32:15

TEST COMMENT: IF-Strong B-B in 9 min
ISI-Weak 1/4" blow
FF-Strong B-B in 16 min
FSI-Weak 1/4" blow

PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2133.01	101.64	Initial Hydro-static
4	42.94	105.59	Open To Flow (1)
20	75.34	109.58	Shut-In(1)
66	1253.31	113.58	End Shut-In(1)
67	81.84	113.00	Open To Flow (2)
87	128.33	113.62	Shut-In(2)
132	1237.42	116.16	End Shut-In(2)
134	2093.89	115.92	Final Hydro-static




Recovery

Length (ft)	Description	Volume (bbl)
90.00	MCGsyO 10%g 70%o 20%m	0.99
215.00	CGsyO 10%g 90%o	3.02
0.00	496 GIP	0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc
Box 399
Garden City Ks 67846
ATTN: Cecil O'Brate

Phyllis # 1-32
32-18-21-Ness-Ks
Job Ticket: 38134 **DST#: 1**
Test Start: 2010.02.22 @ 20:15:15

Mud and Cushion Information

Mud Type: Gel Chem
Mud Weight: 9.00 lb/gal
Viscosity: 53.00 sec/qt
Water Loss: 7.80 in³
Resistivity: ohm.m
Salinity: 2800.00 ppm
Filter Cake: inches

Cushion Type:
Cushion Length: ft
Cushion Volume: bbl
Gas Cushion Type:
Gas Cushion Pressure: psig
Oil API: 36 deg API
Water Salinity: ppm

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
90.00	MCGsyO 10%g 70%o 20%m	0.989
215.00	CGsyO 10%g 90%o	3.016
0.00	496 GIP	0.000

Total Length: 305.00 ft Total Volume: 4.005 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:
Laboratory Name: Laboratory Location:
Recovery Comments:

