



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

American Warrior Inc
Box 399
Garden City Ks 67846
ATTN: Cecil O'Brate

Schugart # 1-26

26-18-22-Ness-Ks

Job Ticket: 039925

DST#: 1

Test Start: 2010.08.16 @ 12:25:06

GENERAL INFORMATION:

Formation: **Miss**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 14:29:21

Time Test Ended: 19:26:51

Test Type: Conventional Bottom Hole

Tester: Dan Bangle

Unit No: 38

Interval: 4253.00 ft (KB) To 4260.00 ft (KB) (TVD)

Total Depth: 4260.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: 2171.00 ft (KB)

2163.00 ft (CF)

KB to GR/CF: 8.00 ft

Serial #: 8354 Inside

Press@RunDepth: 167.58 psig @ 4254.00 ft (KB)

Start Date: 2010.08.16

End Date:

2010.08.16

Start Time: 12:25:07

End Time:

19:26:51

Capacity: 8000.00 psig

Last Calib.: 2010.08.16


Time On Btm: 2010.08.16 @ 14:27:51

Time Off Btm: 2010.08.16 @ 17:36:06

TEST COMMENT: IF-Strong B-B in 30 min

FF-Strong B-B in 40 min

Pressure vs. Time



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2209.88	111.39	Initial Hydro-static
2	21.98	111.70	Open To Flow (1)
47	101.66	122.37	Shut-In(1)
91	1309.11	122.78	End Shut-In(1)
92	106.22	122.23	Open To Flow (2)
137	167.58	123.07	Shut-In(2)
183	1295.24	123.32	End Shut-In(2)
189	2128.61	120.56	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
350.00	Wtr	4.64
10.00	CO	0.14

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc
Box 399
Garden City Ks 67846
ATTN: Cecil O'Brate

Schugart # 1-26
26-18-22-Ness-Ks
Job Ticket: 039925 **DST#: 1**
Test Start: 2010.08.16 @ 12:25:06

Mud and Cushion Information

Mud Type: Gel Chem
Mud Weight: 9.00 lb/gal
Viscosity: 54.00 sec/qt
Water Loss: 9.59 in³
Resistivity: ohm.m
Salinity: 4100.00 ppm
Filter Cake: inches

Cushion Type:
Cushion Length: ft
Cushion Volume: bbl
Gas Cushion Type:
Gas Cushion Pressure: psig
Oil API: deg API
Water Salinity: ppm

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
350.00	Wtr	4.636
10.00	CO	0.140

Total Length: 360.00 ft Total Volume: 4.776 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #:
Laboratory Name: Laboratory Location:
Recovery Comments:

