


KANSAS CORPORATION COMMISSION

23-18-24W

WELL RECORD

15-135-20219

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Lease Name: Debes Well No. 1
 Well Located: Ness County, Kansas
C NW NW SEC 23 TWP 18S RGE 24W
 Operator: Tilco ET AL
 Address: 200 West Douglas, Wichita, Kansas
 Elevation: Ground 2274 D.F. 2276 K.B. 2279
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: 12-16 1968 Drilling Completed: 12-28 1968
 Well Completed: 12-28 1968 Total Depth 4292
 Initial Production: _____

Casing Record

Size: 8 5/8" Set at 290' Size: _____ Set at _____
 Size: 5 1/2" Set at 4288 Size: _____ Set at _____

Liner Record

Size: _____ Set from _____ To _____

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8 5/8"</u>	<u>200</u>	<u>2% Ca. Chl.</u>
<u>5 1/2"</u>	<u>100</u>	<u>50/50 poz. mix</u>

Perforations

Formation	Perforated Interval and Number Shots
_____	_____
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)

25232

Show Drill Stem Tests, 23-18-24w
Well Stimulation and
Production Tests

Formation	Top	Bottom	
Heebner	3637		DST #1 4180-4205 Open 1 hr. Rec. 90' SOC wtry: Mud 60' W FP 37-93# 30" 1 & FBHSIP 1319-1287#
Toronto	3653		
Lansing KC	3678		DST #2 4238-81 Open 1 hr. Rec. 10'M FP 0-0# 30" FBHSIP 150#
Ft. Scott	4177		DST #3 4236-91 Mis-Run
Cherokee	4203		
Mississippi	4274		DST #4 4239-91 Open 1 hr. Rec. 120' HO&GCM 420' V HO & GCM FP 140-330# 30" 1 & FBHSIP 1300-1250#
RTD	4291		