

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.

15-135-21639

S. 24 T. 18 R. 24 ^X/_W
 Loc. C NW SW NE
 County Ness

API No. 15 — 135 — 21,639
 County Number

Operator
Petroleum, Inc.

Address
300 West Douglas Wichita, Kansas 67202


Well No. # 1 Lease Name
Kramer "B"

Footage Location
1650 feet from (N) (~~S~~) line 2310 feet from (E) (~~W~~) line

Principal Contractor Strata Drilling Geologist Jerry Green

Spud Date 6-5-79 Total Depth 4315' P.B.T.D.

Date Completed 7-6-79 Oil Purchaser
Koch Oil Company



Locate well correctly
 Elev.: Gr. 2287
 DF 2290 KB 2292

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	319'	Common	200	2% Gel 3% CC
Production	7-7/8"	5 1/2"	14#	4310'	50/50 Pox	100	10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8" OD	1822'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production <u>7-13-79</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>33</u> bbls. Gas <u>43</u> bbls. Water <u>43</u> bbls. Gas-oil ratio <u>CFPB</u>
Disposition of gas (vented, used on lease or sold)	Producing interval(s) <u>24 hr.</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

25262

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Operator PETROLEUM, INC.		
Well No. 1	Lease Name Kramer 'B'	Oil Well
S 24 T 18S R 24 ^K W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4057-4115', packer failure.			<u>E. L. TOPS</u>	
DST #2 4057-4115', 15-30-30-30. Rec. 10' drilling mud. IFP 69-69#, FFP 69-69#, ISIP 126#, FSIP 92#.			Heebner	3668
			Toronto	3688
			Ls/KC	3711
			B/KC	4038
			Marmaton	4049
DST #3 4198-4240' 15-30-30-30. Rec. 15' mud w/few oil specks. IFP 57-57#, FFP 57-57#, ISIP 704#, FSIP 161#.			Ft. Scott	4214
			Cherokee	4237
			Cherokee Sd.	4309
DST #4 4278-4315' 15-30-60-120. Strong to fair blow. Rec 1445' clean oil, 540' muddy oil. IFP 80-161#, FFP 253-576#, ISIP 1320#, FSIP 1320#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Office Manager
	Title
	July 20, 1979
	Date