

## KANSAS DRILLERS LOG


State Geological Survey

WICHITA, BRANCH

API No. 15 — 135 — 21,008  
County NumberS. 24 T. 18 R. 24 <sup>R</sup><sub>W</sub>

Loc. C NE NW

County Ness

640 Acres  
N

Locate well correctly

Elev.: Gr. 2278'

DF. KB 2282'

Operator

Strata Drilling Co.

Address

Box 355 Great Bend, Kansas

Well No.

#2

Lease Name

Pfannenstiel

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Strata Drilling Company

Geologist

Harold Steincamp

Spud Date

February 17, 1975

Total Depth

4307'

P.B.T.D.

Date Completed

February 28, 1975

Oil Purchaser

## CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8-5/8"	20#	290.15'	60-40 pozmix	175	3% C. C. 2% gel

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

## INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Strata Drilling Company** 25271 DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:  
**Dry Hole**

Well No. **#2** Lease Name **Pfannenstiel**

S 24 T 18 S R 24 E W

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>FORMATION TOPS</u>  Heebner 3663' Lansing 3702' B.K.C. 4032' Marmaton 4042' Fort Scott 4198' Mississippi 4292'  DST #1 4053'-95' Open 15" SI 30" Open 30" SI 30" Weak blow 10". Recovered 5' mud. BHP 69-58 FP 46-46 & 46-46.  DST #2 4182'-4225' Open 15" SI 45" Open 30" SI 30" Weak blow 15 minutes. Recovered 15' mud. BHP 1230-461 FP 69-69 & 69-69.  DST #3 4266'-4300' Open 15" SI 45" Open 30" SI 30" Weak blow 17 minutes. Recovered 15' mud and 5' oil cut mud. BHP 797-484 FP 46-46 & 58-58.  DST #4 & #5 Were misruns.  DST #6 4268'-4307' Open 15" SI 45" Open 60" SI 45" Good blow. Recovered 5' oil and 360' slightly oil cut water. BHP 1341-1330 FP 58-92 & 115-230.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

RECEIVED  
STATE GEOLOGICAL  
SURVEY OF  
KANSAS

Signature

Title

March 4, 1975

Date