

KANSAS DRILLERS LOG

API No. 15 — 135 — 21119
County Number

Operator

Donald C. Slawson

Address

408 120 Building, Wichita, Kansas 67202

Well No.

#1

Lease Name

Pember 'A'

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Slawson Drilling Company

Geologist

Jack Childers

Spud Date

11/10/75

Total Depth

4350

P.B.T.D.

Date Completed


Oil Purchaser

S. 25 T. 18 R. 24W^E_W

Loc. C NE NW

County Ness

640 Acres
N



Locate well correctly

Elev.: Gr. 2254

DF 2256 KB 2259

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		289'	60/40 poz	225 sx	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD


Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

25284

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry hole		
Well No. #1	Lease Name Pember 'A'			
S 25 T 18 R 24 W				
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface hole	0	295	ANH 1509 (+750)	
Red bed and shale	295	980	HEEB 3642 (-1383)	
Sand	980	1150	TORO 3662 (-1403)	
Shale	1150	1885	LANS 3684 (-1425)	
Red bed and shale	1885	2200	B/KC 3981 (-1722)	
Shale and Lime	2200	3983	MARM 4009 (-1750)	
Lime, Shale and Chert	3983	4106	PAWN 4109 (-1850)	
Lime and Shale	4106	4255	FT SCT 4191 (-1932)	
Lime, Shale and Chert	4255	4284	CHER 4213 (-1954)	
Lime and Shale	4284	4350	MISS 4276 (-2017)	
RTD	4350		LTD 4347 (-2088)	
DST #1 4234-84, (Miss zn), 30-45-45-60, Rec. 73' M w/spts oil, IFP 25-86#, IBHP 723#, FFP 86-103#, FBHP 671#				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	 Signature James C. Remsberg, Petroleum Engineer Title December 2, 1975 Date			