

May, 1936.

Continental #1 Aldrich,
NE SE. 7-18S-25W,
Elevation 2510'

Pre-Pennsylvanian

Mississippian
Unit # 2

Top 4425'
4425-4430

Sub-sea, minus 1915'
4430' T. D.

The material is fine grained dolomite with some pinhole porosity. It is probably cavernous to some extent. Made approx. 100 bbls. oil and a small amount of water.

This pay is Unit 2 of the Mississippian, present from 4970-5125' in the Nat. Refining #1 Wells, 13-23S-30W. It is present from 4385-4490' in our #1 Coleman, 25-17S-25W. It is probably a trap made by the Pennsylvanian covering beveled beds of the Mississippian.