


ORIENTAL OIL COMPANY
Tenny # 2

SEC. 19- T.18 R. 25W.
NE o-SW

Total Depth. 4475'
Comm. 8-30-37 Comp. 10-10-37
Shot or Treated
Contractor
Issued. 6-10-39

County Ness



CASING.
10" 650
7" 4335

200' of 5" liner 4470

Elevation. 2507

Production 25 b.O. 220 b. W.

Figures Indicate Bottom of Formations.

Shale and sand shells	170	Broken lime	3150
Shale and sand shells	505	Shale	3155
Sand	545	Lime	3180
Shale and shells	649	Shale	3190
Shale and lime shells	677	Shale and limo shells	3245
Sandy shale	738	Lime 32	3255
Shale	800	Shale	3276
Sand	820	Limo	3320
Shale	970	Shale	3333
Shale and broken sand	1150	Lime and shale, broken	3420
Shale	1160	Shale	3432
Limo	1190	Lime	3455
Shale	1228	Broken lime	3483
Red rock and shale	1250	Lime	3530
Sand and shale	1464	Shale	3555
Sand	1550	Lime	3587
Red rock and shale	1625	Shale	3617
Sand	1635	Lime	3635
Red Rock	1682	Shale	3640
Shale	1760	Lime	3643
Lime	1815	Shale	3685
Shale	1845	Lime	3690
Lime and shale, broken	1905	Shale	3695
Shale and red rock	1980	Lime	3725
Shale	2225	Shale	3776
Sand and limo	2235	Lime	3780
Broken lime	2240	Shale	3802
Salt and blue shale	2355	Lime	3832
Lime	2395	Limo, hard	3875
Shale	2480	Lime	3920
Lime	2490	Hard lime	3930
Shale	2505	Sandy limo and shale	3950
Lime	2535	Lime	3955
Salt	2540	Sandy lime, broken	3975
Broken lime	2585	Lime	4002
Broken lime and Shale	2615	Sandy lime	4014
Shale	2653	Hard Lime	4021
Lime, broken	2660	Lime	4028
Lime	2720	Shale	4035
Lime, hard	2740	Limo	4039
Lime	2768	Shale	4047
Shale	2789	Lime	4086
Lime	2815	Shale and sandy limo	4100
Broken lime	2840	Limo, broken	4122
Hard limo	2873	Lime	4153
Lime	2875	Lime	4194
Shale	2920	Broken lime and shale	4234
Hard Lime	2932	Limo	4237
Shale and broken lime	2942	Shale	4245
Lime	2945	Broken lime	4261
Shale	2978	Lime	4262
Lime	3010	Shale	4274
Shale	3118	Hard lime	4290
Hard Lime	3125	Shale	4294
Shale	3127	Lime	4299
		Shale	4306
		Lime	4317
		Lime, broken (over)	4327

Oriental Oil Company
Tenny # 2 19-18-25W.

Shale	4334
Lime	4350
Slate	4353
Lime	4390
Lime, hard	4410
Black shale	4425
Lime	4452
Lime	4475

TOTAL DEPTH. 4475

Oil 4444 - 4450