

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

6-18-3W

Company- RUPP FERGUSON OIL CO.
Farm- Landgren "A" No. 2

SEC. 6 T. 18 R. 3W
SW SE NW

Total Depth. 3528

Com. n. 2-28-55


Comp. 3-11-55

County McPherson
KANSAS

Shot or Treated.

Contractor. Rupp-Ferguson Oil Co.

Issued. 6-11-55



Elevation. 1381 KP

Production. 25 bbls. oil

CASING:
13 3/8" 188' com. w/200
8 5/8" 409' com. w/125 sx
5 1/2" 3524 1/2' com. w/50 sx

Figures indicate Bottom of Formations

shale	295
shale & sand	370
lime & shale	408
lime & shale strks	645
shale & lime	1195
shale & shells	1830
shale	2020
lime & shale	2100
shale & shells	2230
Miss.	3176
lime & shale	3309
shale	3409
lime & shale	3478
Viola	3528
Total depth	

Tops:	
Mississippi	2943
Kinderhook	3184
Maquoketa	3409
Viola	3463
Simpson shale	3518
Simpson sand	3523
Rotary Total depth	3528

DST 3458-78/ 1 hr. rec. 5' drlg. mud,
BHP 28#.
DST 3516-22/2 hrs. Rec. 120' slightly
gassy oil, 30' muddy oil cut water,
120' muddy water. BHP 1070#.
Cleaned out to TD shot with 13 shots
3528 1/2 to 3424. Swab. 3 1/3 BFPH, 40%
water. POP.