

3-18^s13^w

RIEDL #1

LOCATION

SW SW SW

DESCRIPTION

Sec. 3-18S-13W
Barton County, Kansas

ELEVATION

OWLL

1811 RB
1808 DF
1805 Gr

Date spudded

9-7-50

Date Halliburton Elec. Log

9-19-50

Date plugged

9-22-50

GEOLOGICAL DATA

3054 RB

Ten pieces white lime, stain

3064 RB

Brown and buff lime

3072 RB

Some cherty lime

3077 RB Lansing Kansas City

3098 RB

45' sample, white, dense lime

3100 RB

Vugular poros. Some stain

3115 RB

Vugular poros. Some stain

Slightly vugular lime with poor stain
in few pieces

D.S.T. #1 3079-3115 open 30 min.

Rec. 6' mud

3124 RB

Slightly vugular lime with poor staining

3145 RB

Slightly oolitic lime N.S.O.

3160 RB

Oolitic, porous lime with staining
in spots, mostly white and very good
porosity

3208 RB

Vugular and slightly oolitic lime with
fair to poor porosity and a very slight
show of oil

3226 RB

Vugular with poor porosity and very
slight show of oil

3244 RB

Slightly oolitic and very slight show
of oil

3312 RB Conglomerate

3324 RB Arbuckle

3370 RB T.D.