



8-72W Map No. K-52

OPER KATEX OIL CO.

BORGER, TEXAS


WELL #1 STEINBERG

OR MURFIN DRLG. CO.

WC UNNAMED DISCOVERY

I.P. GA 1,000,000 CFGPD, SIP 410#,

KRI 2747 $\frac{1}{2}$ -48 $\frac{1}{2}$



S-T-R 26-18S-31W

SPOT C NE NE SW

CO SCOTT (KS)

ELEV 2927 KB

B/CM ANH	2264	+654
HOLL	2702	+216
HERR	2713	+205
KRI	2742	+176
B/KRI	2769	+149
WINF	2791	+127
LTD	2802	+116
RTD	2800	+118

SPD 6-28-66 8-5/8" @250/100 SX BILL ATKINSON, GEOL

NO DST'S - RTD 2800' - SCHLUMBERGER LOG - 4 $\frac{1}{2}$ " @2800/100 SX

MITT, CO, PF 4-2747 $\frac{1}{2}$ -48 $\frac{1}{2}$ (KRI)

500A, 8 SG, SIP 410#/6 DAYS, FRAC 2000 GAL (3%)

A + 2000#SD + 22 TONS CO² & FLUSH W/50 BW, GA 887,000 CFG

PD (WET) GA APPROX 1,000,000 CFGPD

GA 1,000,000 CFGPD, SIP 410# (KRI 2747 $\frac{1}{2}$ -48 $\frac{1}{2}$)

COMPLETED 8-9-66 (UNNAMED DISCOVERY) (NOTE: HELIUM CONTENT NOT CHECKED)

Data Inc

MISCEL DATA	GEOL <u>BILL ATKINSON</u>	ELEV <u>2924 DF</u>	SPUD DATE <u>6-28-66</u>
	FTG _____	<u>2918 GR</u>	DRLG COMP _____
	SUPPT _____		FR by DATA <u>6-27-66</u>
	CSG <u>8" 250 W/100 SX.</u>	<u>4$\frac{1}{2}$" 2800 W/100 SX.</u>	COMP by " <u>8-11-66</u>