

MAP NO. _____ 3-9-61 ELEV. 2977 KB 2973 PT
 STATE Kansas COUNTY Scott SEC. 23 Twp 18 S Rge 32 W
 OPERATOR Imperial Oil of Kansas LOC. C NE SW
 WELL NO. 2 FARM NAME Newby FT. FROM. _____ LINE
 POOL Newby (PD 4875) FT. FROM. _____ LINE
 FR. 1-11-61 SPUD 1-4-61 COMP. 2-21-61
 CONT./GEOL. Company tools

NAME PRODUCING INTERVAL	COMPLETION RECORD		TREATMENT RECORD
	FROM - TO	PERF. W/HOLES	
a <u>Mississippian</u>	<u>4577-83</u>	<u>24</u>	<u>3555 Ac</u>
b _____	_____	_____	_____
c _____	_____	_____	_____
d _____	_____	_____	_____

a I. P. OIL/DIST. P/100 EOPD tr GAS _____ M.C.F.P.D. _____ CHK. P HRS. 24
 b " " (calc fr 8 hr test) " "
 c " " " " "
 d _____

D & A

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. 31° PBTD _____ TD 4740

SIZE	DEPTH	CASING - CEMENT RECORD	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>306</u>	<u>275</u>		
<u>5 1/2"</u>	<u>4739</u>	<u>225</u>		

OPERATOR Imperial Oil of Kansas WELL NO. 2 Newby ELEV. 2977 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Base Anhydrite	2295				
Topeka	3643	T*			
Heebner	3882				
Toronto	3902	T			
Lansing	3931	T*			
Base Kansas City	4316	T			
Marmaton	4342	T*			
Cherokee	4491	T*			
Mississippian	4576	T*			
Spergen	4706				
Spud 1-4-61. 8-5/8" @ 306 w/275 sx.					
DST # 1 (Top) 3778-3800, op 1 hr, rec 60' mud spkd oil, ISIP 920/30 mins, no FP, FSIP 820/30 mins.					
DST # 2 (Lans) 3927-51, op 1 hr, rec 90' oil spkd M, ISIP 1070, no FP, FSIP 970.					
DST # 3 (Lans) 3951-73, op 2 hrs, rec 300' oil + 240' MCO + 200' VHOCM + 60' OCW, ISIP 700, no FP, FSIP 650.					
DST # 4 (Lans) 4014-40, op 2 hrs, rec 350' MCSW, ISIP 1050, no FP, FSIP 800.					