

33-18S-34W

THOREN #1

Lauck Drilling Co. - Contractor
Rig #2

C NE NE Sec. 33-18S-34W
Scott County, Kansas

D. R. Lauck Oil Co., Inc. - 1/2
W. C. McBride, Inc. - 1/2

ELEVATION 3131 GL

3134 DF

COMMENCED 4-11-64

3136 KB

COMPLETED _____

INIT. PROD. _____

CASING 290' 8-5/8" w/180 sx Cmt. & 4 sx CaChl.

Call point 3900
Stop 4100 est LCC 4050

FORMATION TOPS:

		Sample
<u>1964</u>		Heebner 3995-859
		Toronto 4011-875
		Lansing 4041-905
		B/K.C. 4417-1281
		Marmaton 4441-1305
		Cherokee 4625-1489
4-13	2005' drlg.	
4-14	2630' "	
4-15	3070' "	
4-16	3345' "	
4-17	3525' "	
4-18	3840' "	
4-19	4100' "	
4-20	4295' "	
4-21	4410' "	
	DST #1, 4307-47, open 1 hr. w/strong blow. Rec. 1635' SW. ISIP & FSIP 1191#/30 min. IFP 175#, FFP 735#.	
4-22	4534' drlg.	
4-23	4620' "	
	DST #2, 4542-62, open 1 hr. w/good blow. Rec. 900' oil specked salt water. ISIP 1240#/30 min. FSIP 1172#/30 min. IFP 149#, FFP 410#.	
4-24	4737' drlg.	
4-25	4830' drlg.	
	DST #3, 4807-30, open 30 min. w/weak blow 2 min. & died, flushed tool. Rec. 20' mud. ISIP 380#/20 min. FSIP 119#/20 min. IFP 14#, FFP 29#.	
4-27	4956' drlg.	

OWLL

THOREN #1

Lauck Drilling Co. - Contractor
Rig #2

C NE NE Sec. 33-18S-34W
Scott County, Kansas

D. R. Lauck Oil Co., Inc. - 1/2
W. C. McBride, Inc. - 1/2

ELEVATION _____ GL

_____ DF

_____ KB

COMMENCED 4-11-64

COMPLETED _____

INIT. PROD. _____

CASING 290' 8-5/8" w/180 sx Cmt. & 4 sx CaChl.

Call point 3900
Stop 4100 est LXC 4050

FORMATION TOPS:

1964

4-13 2005' drlg.

OWLL