

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

2-18-4W

COMPANY O.A. SUTTON OIL PROPERTIES & INVESTMENTS

SEC. 2 T. 18 N. 4W
LOC. CW/2 SE NW

FARM Palmquist

NO. 3

TOTAL DEPTH 3517'

COMM. 5-1-68


COMP. 5-9-68

SHOT OR TREATED

CONTRACTOR Blackstone Drllg., Inc.

ISSUED 7-27-68

COUNTY McPherson
KANSAS



CASING

20	10	
15	8 5/8	432' w/300 sx cem.
12	6	
13	153' w/200 S	
	SX cem.	

ELEVATION 1396' K.B.

PRODUCTION DRY/MAQ.

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	80	Shale
80	to	130	Sand
130	to	153	Blue Shale
153	to	225	Shale & Shells
225	to	265	Gyp. Shale
265	to	535	Anhydrite
535	to	930	Lime
930	to	1920	Shale & Lime
1920	to	2215	Lime
2215	to	2345	Shale & Lime
2345	to	2383	Lime
2383	to	2885	Lansing
2885	to	3023	Cherokee
3023	to	3280	Mississippi
3280	to	3499	Kinderhook
3499	to	3506	Misner
3506	to	3517	Maquoketa
		3517	T. D.

Cut 17 1/4 in. hole to 153 ft. and run 157 ft. of 13 in. and cemented with 200 sacks on bottom at 153 ft. Plug down at 12:00 noon on April 30, 1968. On May 1, 1968 made 11 in. hole to 432 ft. and run 437 ft. of 8 5/8 in. O.D. casing and cemented at 432 ft. with 200 sacks. Plug down at 10:30 P.M. May 1, 1968. Cut 7 7/8 in. hole to 3517 ft. Hole dry and abandoned. Filled hole to 300 ft. with mud, set plug and cemented with 25 sacks. Filled hole to 40 ft. with mud, set plug and cemented with 10 sacks cement. Two sacks in rathole. Hole plugging completed at 4:15PM May 9, 1968 by Hugh Scott, State pluggger, McPherson, Kansas.

TOPS: Misner - 2157' Lansing - 2383' Cherokee - 2885' Mississippi - 3023'
Kinderhook - 3280' Misner - 3499' Maquoketa - 3506'

Measurements taken from K.B.

CERTIFICATE

I, M. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Palmquist #3, located on the C-W/2 SE/4 NW/4 of Sec. 2-18S-4W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

M. J. Plouffe
M. J. Plouffe, President