

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

10-18-4W

COMPANY O. A. SUTTON

SEC. 10 T. 18 R. 4W
LOC. App 100' S of C NE SW

FARM Dahlsten

NO. 1-A

TOTAL DEPTH 3654

COMM. 10-30-66

COMP. 11-13-66


SHOT OR TREATED

CONTRACTOR Gabbert-Jones

ISSUED 2-18-67

COUNTY Mc Pherson

KANSAS



CASING 13 3/8" @ 386' w/400 SX

20

10

15

8

5/8" @ 512' w/250 SX

12

6

13

5

ELEVATION 1463' KB

PRODUCTION DRY (VIOLA)

FIGURES INDICATE BOTTOM OF FORMATIONS

From	To		
0	386	Sand and shale	Ran 20 joints of 13-3/8" casing set @ 386' w/400 sacks cement.
386	495	Shale	
495	512	Lime	Ran 18 joints of 8-5/8" casing set @ 512' w/250 sacks cement.
512	790	Shale and shells	
790	1380	Shale and lime	
1380	1760	Shale and shells	
1760	2486	Shale and lime	
2486	2543	Lime	TOPS: SCOUT
2543	2760	Shale and lime	
2760	2970	Lime	Heebner 2254
2970	3088	Lime and shale	Lansing 2466
3088	3120	Chert and chat	Mississippi 3099
3120	3200	Shale and chert	Kinderhook 3333
3200	3310	Lime	Maquoketa 3561
3310	3335	Cherty lime and shale	Viola 3621
3335	3568	Shale	
3568	3613	Shale and lime	
3613	3622	Shale and dolomite	
3622	3640	Lime and shale	
3640	3654	Lime	
3654	TD		Ran 32 joints of 5-1/2" casing set @ 996' w/180 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled Approx. 100' S of C NE SW Section 10-18-4W, McPherson County, Kansas, to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Before me, the undersigned, a Notary Public within and for said County and State, on this 15th day of November, 1966, personally appeared E. E. HALL, to me