


Olson
LEASE

1
WELL NO.

1
TEST NO.

K & E Drilling, Inc.
COMPANY


Kansas
DISTRICT



OIL WELL CEMENTING CO.

Formation Testing
"Service Report"

TIME



Each Horizontal Line Equal to 1000 p.s.i.

Olson
LEASE1
WELL NO.1
TEST NO.K & E Drilling, Inc.
COMPANYKansas
DISTRICT

LOCATION 2-18-4W
FIELD Wildcat
COUNTY McPherson
STATE Kansas
CONTRACTOR Deek
Drilling, Inc.

MUD DATA

Kind Starch
Weight 9.9 lbs.-gal.
Viscosity 40 Sec.
Filter Loss 17.2 c. c. Filter Cake 2/32 in.
BT. P.R.D. No. 312 Blanked Off No

12 Hr. Clock No. 922
Est. Gauge Depth Temp. 100 °F

Pressure Readings	Field	Office Corrected
Initial Hydro Mud Pressure		1881 p.s.i.
Initial Flow Pres.		15 p.s.i.
Tool Open	60 minutes	
Final Flow Pres.		20 p.s.i.
Time Closed In	15 minutes	
Closed in Pres.		1225 p.s.i.
Final Hydro Mud Pressure		1855 p.s.i.

HOLE & TOOL DATA

Total Depth	3540'	Casing Perforations	Top	
			Bottom	
Top Packer Depth	3532'	Bottom Packer Depth	-----	
Casing or Hole Size	7 7/8"	Liner or Rathole Size	7 7/8"	
Formation Tested	Misener Sand			
Size Drill Pipe	4 1/2" APIFH	Size Drill Collars	5 3/4" x 63'	
Size Bottom Choke	1/2"	Size Surface Choke	1"	
Size Tool Valve	1"	Size Pilot Valve	-----	
Size Hook Wall Packer	-----	Size Rings	-----	
Size D. E. Wall Packer	6 3/4" DEWP	No. Packers	One	
PRD Device No.	1534	Blanked Off	No	
Size & Length Anchor	8' of 3 1/2" Perforated			

REMARKS: Opened tool with a weak blow that decreased until it died in 13 minutes. Recovered 23' of watery drilling mud.

Amount of Cushion None

All depths measured from Kelly Bushing

Date June 2, 1952
Ticket No. 42581-T
HOWCO District McPherson
Kind of Job Open hole test
Price \$215.00
Second Packer Assembly -----
Safety Joint -----
Extra Folder Charge -----
Jars -----
Total \$215.00
Witnessed By Jack H. Brown
Tester G.D. Mills

No. Folders Reproduced Five