

11-54W

WILDCAT

SEC. 5-18S-41W

STATE Kans COUNTY Greeley

LOC C NW SW

OPER. Terrel Drilling & Producing - Russell, Kansas

FT/FR LINE

WELL 1 FARM Wheeler

FT/FR LINE

WC ELEV. 3720 GR. 3722 DF 3725 KB


Co. tools GEOL. Ray Goodin

INT. 5400' Miss Test

F.R. 8-31-64 SPUD 9-7-64 COMP. 11-3-64

TD 5291 FM. St Lou PBD.

D&A

COMP.
RECORD

WC-26 mi SW of Carwood (Abd Marm Oil) Pool

8 5/8" @165 w/160 sx.

Data Inc.

(KB Spl)

Cim Anh 2558

B/Cim Anh 2584 /1141

Hb 4028

Lans 4084

BKc 4500

Chero 4681

Mrw 4989

Mrw lm 5074

nt Below)

C #1 (Cher-Mrw) 4985-5021, R 36' total

(4' blk to brn lm, 26½' blk to grn platy to blk sh, 1' coal, 4½' grn to blk sh)

C #2 (Mrw) 5021-43, R 22' total (22'

blk sh w/some pyrite incl & sm ls seams at base)

C #3 (Mrw) 5043-70, R 25' total (23' sh,

calc seams & pyritic, in part, 2' lost)

C #4 (Mrw) 5125-60, R 35' total (3½' foss

lm, 3½' lm, cgl, shly, 3' blk sh, 4' foss

St L 5238

RTD 5291

(KB Log)

Cim Anh 2556 /1169

Kri 2792 / 933

Winf 2811 / 914

U/FR 2854 / 871

L/FR 2916 / 809

Hb 4030 - 305

Tor 4052 - 327

LKc 4082 - 357

BKc 4514 - 789

Marm 4542 - 817

Chero 4692 - 967

Mrw 4994 -1269

Mrw lm 5076 -1351

St G 5185 -1460

St L 5238 -1513

LTD 5291 -1566

lm, 1' blk sh, 13½' foss lm, 6½' shly lm)

C #5 (Mrw-St G) 5160-5210, R 50' total

2' lm, shy, foss, 4' lm, foss, 2' lm,

foss, grn sh partings, 1' sh, calc, 8'

lm, foss, galuc, sm fn grn sd, 8' lm,

crs xln, drk brn - highly foss, few ool,

(Top St Gen)-6' lm, fn xln, buff to lt

brn, fn grn sd & sm small ool, 3' as

above w/sm pyrite in seams, 9' lm, fn xln,

lt brn, sli sdy w/drk brn frac in last 3',

7' lm, med xln, lt brn to buff, very ool,

considerable med to crs gr sd, some

quartzitic)

C #6 (St G - St L) 5210-80, R 50' total

(27' lm, lt brn to buff, fn to med xln,

sli sdy, few ool, 1' lm, blk to fn xln,

no ool, (Top St L)-2' lm, banded, no

ool, 10' lm, brn to fn xln, small ool

(Sample Descrip 5255-80 - St L) 5' lm,

lt brn, fn xln, ool, sli chalky, 5' as

above w/lots chalk & few pieces ch, 5' lm w/lots chalk, ool, 10'

lm, fn xln, no ool, RTD 5291, D&A - COMPLETED (10-28-64)