

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey WICHITA BRANCH

S 30 T. 18s R. 6 W

API No. 15 - 159 - 21,237
County Number

Loc. SW SW NW
County Rice

Operator R & B Petroleum, Inc.

Address P.O. Box 1065, Great Bend, Kansas 67530

Well No. 1 Lease Name Carlton

Footage Location 2310 feet from (N) line 330 feet from (E) (W) line

Principal Contractor Allen Drilling Company Geologist Randy Lilak

Spud Date 8/3/81 Date Completed 8/8/81 Total Depth 3225 P.B.T.D.

Directional Deviation 1 1/2 @ 3000 Oil and/or Gas Purchaser

640 Acres N
Grid diagram showing well location (30)
Elev.: Gr. 1634 ft.
DF 1637 ft. KB 1639 ft.

CASING RECORD

Report of all strings set - surface, intermediate, production, etc.

Table with 8 columns: Purpose of string, Size hole drilled, Size casing set (in O.D.), Weight lbs/ft., Setting depth, Type cement, Sacks, Type and percent additives. Rows include Surface and Production data.

LINER RECORD

PERFORATION RECORD

Tables for Liner Record (Top ft., Bottom ft., Sacks cement) and Perforation Record (Shots per ft., Size & type, Depth interval). Tubing Record table below with columns: Size, Setting depth, Packer set at.

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Table with 2 columns: Amount and kind of material used, Depth interval treated. Row: Acid/500 gal. (Dowell XW-35) 2989 - 2995

INITIAL PRODUCTION

Date of first production Aug. 31, 1981 Producing method (flowing, pumping, gas lift, etc.) Pumping Date: AUG 1 1982 FROM CONFIDENTIAL

RATE OF PRODUCTION PER 24 HOURS Oil 2 bbls. Gas MCF 30 bbls. Water Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s) 2989 - 2995

RELEASED AUG 1 1982 FROM CONFIDENTIAL

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209.

Operator
R & B Petroleum, Inc.

Well No. 1 Lease Name Carlton

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil

S 30 T 18SR 6 W SW SW NW

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 2968 - 3000 Times: 60"-60"-90"-90" Rec: 90' 0 & GCM 540' SO & GCSW ISIP: 1207# FSIP: 1174# IFP: 45-170# FFP: 204-306# HP: 1586#			Log Tops: Heebner Douglas Brown Lime Lansing Base KC Marmaton Cherokee Kinderhook Log TD Welox: Gamma, Guard, Sidewall Neutron, Caliper	2550 2587 2679 2729 3077 3085 3140 3188 3225

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received


 Signature
 Robert D. Dougherty - Geologist
 Title
 Oct 27, 1981
 Date

DRILLER'S WELL LOG

DATE COMMENCED: 08/03/81
DATE COMPLETED: 08/08/81

R & B Petroleum, Inc.
CARLTON No. 1
SW SW NW
Sec. 30, Twp. 18S, Rge. 6W,
Rice County, Kansas

ELEVATION: 1634' G.L.
1639' K.B.

FORMATION DATA:

Tight hole

SURFACE PIPE:

Ran 5 jts. 20# new 8-5/8"
casing; tally: 206';
Set @ 213' w/ 130 sks 60/40
poz., 2% gel, 3% cc, plug
down @ 7:30 PM, 8/3/81
By Sun

PRODUCTION PIPE:

Ran 78 jts. 9.5# 4 1/2" csg.
Tally: 3234'; Set @ 3224'
w/ 125 sks 60/40 poz, 18%
salt, 15 bbl. salt flush,
Plug down @ 11 AM, 8/8/81
By Howco

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1981

CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Roy Goans, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best