


SW SE NE

3-18-7W

API # 15-159-20,414

KANSAS

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579



WELL LOG ----- C. A. CLICK #1
Located: SW SE NE, Section 3-18S-7W, Rice County, Kansas

OWNER: L. H. Pearson
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

RECEIVED
STATE CORPORATION COMMISSION

COMMENCED: February 10, 1972
COMPLETED: February 20, 1972

MAR 13 1972

CONSERVATION DIVISION
Wichita, Kansas

TOTAL DEPTH: 3553'

LOG

CASING RECORD

0 - 100	Shale
100 - 226	Shale and Lime
226 - 237	Lime
237 - 267	Soft
267 - 1055	Shale - Salt and Lime
1055 - 2307	Lime and Shale
2307 - 2475	Lime
2475 - 2677	Lime and Shale
2677 - 2755	Lime <i>Lime</i>
2755 - 2985	Lime and Shale
2985 - 3180	Lime
3180 - 3185	Lime and Shale
3185 - 3190	Lime and Shale - Sand
3190 - 3194	<i>Sand</i>
3194 - 3242	<i>Sandy Lime Sandy Lime</i>
3242 - 3265	<i>Lime Lime</i>
3265 - 3462	Lime and Shale
3462 - 3580	Lime and Shale and Chert
3580 - 3553	Lime <i>Lime</i>

Ran 6 joints 8 5/8", 20#, 8rd, Rge.
3 new casing. 231' set at 243' K.B.
with 160 sacks 60/40 Pozmix with
Quickset. Plug down @ 11:45 PM,
2-10-72.

LOG TOPS

HEEB	2494
BN LM	2714
LANS	2754
BKC	3104
CONG SD	3173
MISN SD	3242
LTD	3283

SAMPLE TOPS

MAQ	3288
SIMP	3446
ARB	3483
RTD	3554

Plugged.

