


CONTINENTAL OIL CO.
D. M. Siemsen No. 1.

SEC. 18 T. 18 R. 7W
NWc NW
330'S 330'E NW Cor.

Total Depth. 3188'
Comm. 11-25-38 Comp. 12-9-38
Shot or Treated. 2000 Gals.
Contractor.
Issued. 2-4-39

County. Rice



Elevation.

CASING:
10^{3/4}" 207'
7 " 3183'

Production. Pot. 954.66 B.
No water

Figures Indicate Bottom of Formations.

cellar	8 ¹ / ₂
surface hole	207
shale & shells	700
salt	1050
shale & shells	1363
sand	1375
brkn lime	1585
brkn lime & shale	1760
shale & shells	2350
brkn lime	2440
lime	2655
shale & shells	2742
lime	3120
shale & lime	3165
shale	3184
Arbuckle dolomite	3186
lime	3188
Total Depth.	

Top of Arbuckle lime 3182

Total fillup 2800' with oil

- 12-20-38 On pumping test the well pumped 140 BO in 2¹/₂ hrs & pumped down
- 12-21-38 The well was acidized w/2000 Gals.
- 12-22-38 On initial potential test the well pumped 318.22 BO 8 hrs, giving the well a 24-hr potential of 954.66 BO -No wtr.