


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.  
D.M. Siemsen No. 4

SEC. 18 T. 18 R. 7W.  
SE NW NW  
990' S 990' E of NW cor

Total Depth. 3225  
Comm. 7-6-39 Comp. 7-19-39  
Shot or Treated. 1000 gal Acid.  
Contractor.  
Issued. 9-23-39

County Rice.



CASING.

103/4" 210'  
7" 3221'

Elevation.

Production. Pot. 1938. 15 B.

Figures Indicate Bottom of Formations.

shale and shells	210	
shale	505	
shale and shells	1030	
broken lime	1150	
shale	1205	
shale and lime shells	1342	
shale and shells	1400	
broken lime	1467	
lime	1640	
shale	1657	
broken lime	1745	
shale	1905	
shale and shells	1977	
shale and salt	2088	
shale	2096	
lime	2150	
broken lime	2188	
shale and lime shells	2270	
shale and shells	2370	
broken lime	2394	
lime	2600	
shale	2643	
shale and shells	2782	
lime	2855	
broken lime	2878	
lime	2890	
lime soft	2908	
lime	2940	
lime soft	2950	
lime	2975	
lime hard	2977	
lime soft	2990	
lime	3150	
conglomerate	3170	
lime hard	3175	
shale	3220	
Arbuckle dolomite	3222	show oil
Core lime	3225	
Total Depth.		

Top of Arbuckle lime from cement floor level 3219

Total Depth from cement floor level 3224

Cored from 3222 to 3225 with a 2' rec. of Arbuckle lime spotted shows of oil

Total Fill up with oil 2000'

7-27-39 acidized with 1000 gal acid.

7-28-39 On initial potential test the well pumped 646.05 bbls of oil  
in 8 hours giving the well a 24 hour potential of 1938.15 bbls oil  
no water.

Total Depth from cement floor level 3224.

Arbuckle lim 3219-3224