


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
B. C. Gray No. 1.

SEC. 19 T. 18 R. 7W
NWc SW
330'S 330'E W $\frac{1}{4}$ Cor.

County. Rice



Elevation. 1696

Production. Pot. 2770 B.
no wtr. Nat.

Figures Indicate Bottom of Formations.

shale & shells	206
shale & red rock	880
salt	1030
shale & shells	1110
shale & lime	1193
shale & shells	1305
shale & lime	1480
lime	1575
shale & shells	2325
shale & lime	2420
lime	2610
shale & shells	2768
lime	3025
shale & lime	3100
lime Arbuckle	3109
lime	3176
Total depth from cement floor level	3175
Total Depth.	

3098
1696

1402

Top of Arbuckle lime from
derrick floor 3098

Total fillup with oil 3000'
7-26-39 on initial potential
test the well pumped 923.48
bbls oil in 8 hrs giving the
well a 24-hr potential of
2770 bbls oil, no wtr.
Natural, no acid was used.