


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
B.C.Gray No. 5

SEC. 19 T. 18 R. 7 W.
SW NE SW
990' S & 990' W of Center

Total Depth. 3200 (3199 Cem.Fl.L.)
Comm. 2-9-42 Comp. 2-26-42
Shot or Treated.
Contractor.
Issued. 5-16-42

County Rice.



CASING.

10 3/4" 212' cemented.
6" 3175' cemented.

Elevation.

Figures Indicate Bottom of Formations.

Production. Pot. 3000 B.
Echometer. No wtr.
(Ind.Cap.6488 B.)

surface clay	15
shale	115
shale and shells	825
salt	975
broken lime	1503
shale and shells	1725
lime	1765
shale and shells	1997
broken lime	2340
lime	2624
broken lime	2705
lime	2880
lime soft	2891
lime	3106
shale	3145
sand	3154
lime	3159
sand	3175
lime	3200
	3199 Total Depth from cement floor level.

Top Arbuckle 3174

Total Fillup with oil 3100'

Established an Echometer Potential of 3000 B. of oil,
no water, Indicated capacity 6488 bbls..

Note - All of above footages are calculated from the cement floor level.