


CONTINENTAL OIL CO.
Wm. Hamilton "A" No. 3.

SEC. 19 T. 18 R. 7W
SE NW NW
990'S & E NW Cor.

Total Depth. 3228' PB 3227' (CFL 3226)
Comm. 1-7-41 Comp. 1-22-41
Shot or Treated.
Contractor.
Issued. 5-3-41

County. Rice



CASING:
10 3/4" 208' Cem.
6" 3221' Cem.

Elevation.

Production. Pot. 2270 B. Echo.
120 BW

Figures Indicate Bottom of Formations.

surface sand, clay & shells	40
shale & shells	1005
salt	1035
shale & shells	1201
lime	1290
lime brkn	1450
lime brkn & gyp	1527
lime brkn	1836
shale & shells	2380
lime	2420
lime brkn	2481
shale & shells	2540
lime	2600
lime brkn	2680
shale & shells	2718
lime	2860
shale brkn	2870
lime brkn	2890
lime sft-oil odor	2912
lime brown	2940
lime hrd	2958
lime sft & shale	2965
lime med hrd	2987
shale & lime	3000
lime	3045
lime hrd	3108
shale & lime	3167
lime hrd	3170
shale & lime	3221
lime	3228
Total Depth.	

Plugged back 1' to 3227

Total depth from cement floor
level 3226

1-16-41 Cored from 3215-21 rec 5'
of green shale

1-17-41 Cored from 3221-29 8' rec.
of Arbuckle lime w/good
show of oil

Top of Arbuckle lime from cement
floor level 3219

Total fillup w/oil 3000' - Swabbed
226 BO in 3 hrs, swabbing down to
1200' - Bailed 3 BWPB from btm

1-27-41 Plugged back to 3226 in
Arbuckle lime - Hole filled up
2000' w/oil in 2 hrs-sm amt wtr

1-29-41 Established an Echometer
Potential of 2270 BO, 120 BW