


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
S. Ainsworth No. 4-A

SEC. 30 T. 18 R. 7W.
NW SW NW
330' E. 990' N of W $\frac{1}{4}$ cor

Total Depth. 3223
Comm. 5-14-38 Comp. 5-29-38
Shot or Treated.
Contractor.
Issued. 10-8-38

County. Rice.



Elevation.

Production. Dry.

CASING.

103/4" 202'

Figures Indicate Bottom of Formations.

soil	20
shale and sand	202
shale and red rock	430
red rock and shale	760
salt	980
shale and sholls	1340
sand	1360
limo	1440
limo	1460
shalo	1535
shale and sholls	2055
broken limo	2100
shalo	2120
shale and sholls	2325
limo	2630
shalo	2665
shale and sholls	2760
limo	2825
limo	3110
shale and sand	3120
conglomerato	3156
limo and shale	3162
conglomerato	3189
conglomerato	3198
Arbucklo limo	3223
Total Depth.	

Cored from 3156 to 3162 with 4' Rec. of conglomerato and limo No show.

Top of Arbucklo. limo 3198

Cored from 3203 to 3206 with 3' Recovery of limo Spotted oil shows.

May 27, 1938 A Halliburton Drill stem test was taken from 3198-3206.
The test showed 10' of water and mud with a slight trace of oil water is salty.

May 29, 1938 a Second Halliburton Drill stem test was taken from 3198 to 3221. after the well was drilled to a total depth of 3221. Result of the test 80' Sulphur and salt water.