


CONTINENTAL OIL CO.  
A. H. Meyers No. 4.

SEC. 30 T. 18 R. 7W  
SEc SW  
255' W 330' N S $\frac{1}{4}$  Cor.

Total Depth. 3180'  
Comm. 10-22-38 Comp. 11-9-38  
Shot or Treated. 3000 Gals.  
Contractor.  
Issued. 12-31-38

County. Rice



CASING:  
10 $\frac{3}{4}$ " 213'  
7 " 3160'

Elevation. 1697

Production. Pot. 2057 B.  
No water.

Figures Indicate Bottom of Formations.

shale & shells	750
salt	1050
shale & shells	1345
sand & lime	1370
brkn lime	1880
shale & shells	2025
brkn lime	2250
shale, shells, & lime	2325
lime	2390
lime & shale	2487
lime	2565
brkn lime	2600
lime	2905
lime Kansas City	2945
lime	3138
sand	3149
shale	3165
Arbuckle	3167
lime	3180
Total Depth.	

3159  
1697  
-----  
1462

Top Arbuckle lime 3159  
Hole filled up 3100' w/oil, filling  
up at the rate of 700' Per Hr.  
No test on well before acidizing  
On pumping test after acidizing the  
well pumped 371.92 bbls oil 4 hrs.  
On initial potential test the well  
pumped 685.67 bbls oil 8 hrs,  
giving well a 24-hr potential of  
2057 bbls oil, no wtr.