


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.  
A.H. Meyer No. 9

SEC. 30 T. 18 R. 7W.  
SE NW SW  
990' S. & 990' E W/4 Cor.

Total Depth. 3209  
Comm. 4-8-41 Comp. 4-23-41  
Shot or Treated.  
Contractor. L.W. Prunty Drlg. Co., Inc.  
Issued. 7-5-41

County Rice.



CASING.

103/4" 195'  
6" 3172'

Elevation.

Indicated capacity  
Production. Pot. 6306 B.  
No wtr. Echometer,  
Max. Pot. 3000 B.

Figures Indicate Bottom of Formations.

surface clay	25
shale and sholls	1020
broken limo	1158
shale	1185
broken limo	1370
lime	1416
broken lime	1581
shale and sholls	1652
broken limo	1700
shale and sholls	1904
broken limo	2048
shale and sholls	2141
broken lime	2281
lime	2581
broken lime	2727
lime	2875
limo soft	2900
lime	3147
broken lime	3172
dolomite	3187
lime	3209
Total Depth.	

Arbuckle lime 3171 - 3209

Total Fillup with oil 3100, swabbed 188 bbls of oil in 4 hours.

4-24-41 Acidized with 2000 gal.

4-25-41 Established a maximum allowed potential by Echometer  
of 3000 bbls of oil, no water, indicated capacity 6306 bbls.

Note: All of above footages are  
calculated from the cement  
floor.